


SCATOLA CON PASSACAVI

Serie SCABOX


Coperchio	Dimensioni (mm)	N° entrate	Per	Viti di fissaggio	ϕ		
						IP44	IP55
Coperchio a pressione	ø65x35	4xø23mm	PG 16	2	4/100	⊕ 680.001	
	ø65x40	4xø23mm	PG 16	2	4/100		
	ø80x40	4xø23mm	PG 16	2	4/100	⊕ 680.002	
	80x80x40	6xø23mm	PG 16	2	4/60	⊕ 680.003	
		7xø23mm	PG 16	2	4/60		
	100x100x50	6xø23mm	PG 21	4	1/48		⊕ 685.004
7xø23mm		PG 21	4	1/48			
Coperchio a vite	120x80x50	6xø29mm	PG 21	4	1/54		⊕ 685.005
	150x110x70	10xø29mm	PG 21	4	1/40		⊕ 685.006 (K1)
	190x140x70	10xø38mm	PG 29	4	1/24		⊕ 685.007 (K1)
	240x190x90	12xø38mm	PG 29 (♣)	4	1/12		⊕ 685.008 (K1)
	300x220x120	12xø38mm	PG 29 (♣)	4	1/6		⊕ 685.009 (K1)
	380x300x120	12xø48mm	PG 36 (♣)	4	1/4		⊕ 685.010 (K1)
	450x370x130	14xø48mm	PG 36 (♣)	6	1		⊕ 685.011 (K2)

(♣) Adatta per il montaggio del kit cerniere.

(K1) Accetta staffe di fissaggio art. 654.0021.

(K2) Accetta staffe di fissaggio art. 654.0023.

Serie CUBIK


		
IP55 - GW 650°C	IP55 - GW 960°C	IP55 - GW 960°C
⊕ 687.001	⊕ 688.001	
⊕ 687.002	⊕ 688.002	
		⊕ 688.003.R
⊕ 687.003	⊕ 688.003	
⊕ 687.004	⊕ 688.004	⊕ 688.004.R
⊕ 687.005	⊕ 688.005	⊕ 688.005.R
⊕ 687.006	⊕ 688.006	

Serie SCABOX




Ingresso cavo con passacavo o pressacavo; scanalature sul fondo.

ACCESSORI

Descrizione		ϕ		
Kit staffe di fissaggio a parete	K1	4 pezzi	10	654.0021
	K2	4 pezzi	10	654.0023
Kit piombatura (*)			10	654.0032
Kit cerniere			1/20	
Tappi coprivite		12 pezzi	10/100	
Piastra di fondo in acciaio zincato	190x140		1	
	240x190		1	
	300x220		1	
	380x300		1	
	452x372		1	

(*) Per scatole 190x140 - 240x190 - 300x220 - 380x300 - 450x370.

ACCESSORI

		
		654.0085
		654.0080
		654.0787
		654.0788
		654.0789
		654.0790
		654.0791

Serie CUBIK



SCAME
IP55 688.204.R 960°C

Le versioni Glow wire 960°C (anche rosse) sono identificabili dal simbolo riportato esternamente.